MEMORANDUM FOR: All NWS Regional Headquarters, Regional

Maintenance Specialists, Electronic Systems

Analysts, and Electronics Technicians

[Engineering Handbook (EHB-9) distribution]

FROM: W/OPS1 - Mark Paese (Acting)

SUBJECT: Transmittal Memorandum for EHB-9 Issuance 02-07

1. <u>Material Transmitted</u>:

Engineering Handbook No. 9 (EHB-9), Automatic Radiotheodolite (ART-1/2), Section 2.3, Maintenance Note 28, Amplifier Switches P/N SA-23025-0103 or GHG 122 3121D 1003 and Safety Barrier Switch P/N SB0728 with SB9102 Mounting Bracket Installation, Revised Hydrogen Safety Switch Control Box Schematic Drawings

2. <u>Summary</u>:

In the event the amplifier switch or safety barrier switch fails, Maintenance Note 28 provides Amplifier Switches P/N SA-23025-0103 or GHG 122 3121D 1003, and Safety Barrier Switch P/N SB0728 with SB9102 Mounting Bracket installation procedures. A revised J407-Schematic. J407-1 and J407-2 Schematics are included.

3. <u>Effect on Other Instructions</u>:

Discard Modification Note 26 in EHB-9, section 3.3. Substitute pages 14, 15, and 16 in Hydrogen Safety Switch Instruction Manual 9-311 in EHB-9 section 1.3 with the replacement pages included in this maintenance note.

MAINTENANCE NOTE 28 (for Electronics Technicians) Maintenance, Logistics, and Acquisition Division

W/OPS12: FJZ

SUBJECT : Installation of Amplifier Switch P/N SA-23025-0103 or GHG 122 3121D

1003 and Safety Barrier Switch P/N SB0728 with SB9102 Mounting

Bracket

PURPOSE : To provide revised amplifier switch and safety barrier switch

installation instructions

EQUIPMENT : Hydrogen or helium ART-1/2 sites using the hydrogen safety control

AFFECTED box.

PARTS REQUIRED : Amplifier switch (ASN: J407-28) and barrier safety switch

(ASN: J407-29) are stocked at the National Logistics Support Center

SPECIAL TOOLS

REQUIRED

: None.

MODIFICATION : Amplifier switch (ASN: J407-28) and barrier safety switch

PROCUREMENT (ASN: J407-29)

SITES AFFECTED : All ART-1 and ART-2 sites with a hydrogen safety control box.

ESTIMATED TIME

REQUIRED

: 2 Hours

EFFECT ON OTHER:

Discard Modification Note 26 in EHB-9, Section 3.3. Substitute pages

14, 15, 16, and the hydrogen safety switch schematic with the

replacement pages included in this maintenance note (files J407SCH, J407SCH1, and J407-SCH2) in *Hydrogen Safety Switch Instruction*

Manual 9-311 in EHB-9 Section 1.3.

AUTHORIZATION : N/A

VERIFICATION STATEMENT

: This maintenance note was successfully tested at the WFO Green

Bay, WI (GRB)

TECHNICAL

: For questions or problems pertaining to this Maintenance Note, please

ASSISTANCE contact Franz J. G. Zichy at 301-713-1833, x128.

GENERAL:

This maintenance note provides revised amplifier switch and safety barrier switch installation instructions. Also included are the Hydrogen Safety Switch Schematics (files J407SCH, J407SCH1, and J407-SCH2) and replacement parts list. Insert the schematic drawings and parts list into Engineering Handbook No. 9 (EHB-9), *Automatic Radiotheodolite (ART-1/2)*, Section 1.3, Hydrogen Safety Switch Instruction Manual 9-311.

PROCEDURE:

NOTE: Perform this maintenance only if the present amplifier switch and/or barrier switch are defective.

A. Installation of Amplifier Switch

- 1. At the balloon inflation building, locate the main power breaker and turn off the alternating current (AC) power to the inflation building.
- Open the lid of the hydrogen safety switch by loosening the two (2) plastic fasteners, (figure 1).
- 3. With a VOM, verify no AC power exists at TB1 terminals 1 and 2 inside the hydrogen safety switch.
- 4. Remove the leads from the terminals of the amplifier switch (figure 2).
- 5. Loosen the clamp on the left rail mount (figure 2) and remove.



Figure 1




Figure 2

- 6. Remove the old amplifier switch.
- 7. Place the new amplifier switch on the rail mount.
- 8. Replace and tighten the clamp on the rail mount (figure 2).
- 9. Note the Amplifier switch type, and connect the appropriate leads to the amplifier switch terminals. See table 1 and the attached J407-SCHEMATIC drawings.

Table 1

Control Box Part and Terminal Wire Color	Amplifier Switch SA 0025 M 0003 Terminal	Amplifier Switch SA 23025 M0103 Terminal	Amplifier Switch GHG 122 3121D 1003 Terminal
TB2 Terminal (1) (White Wire)	11	4	6
TB2 Terminal (2) (Black Wire)	12	6	7
TB2 Terminal (3) (Red Wire)	7	1	2
24V RTN (Lower Reed) Part 20 (Purple Wire)	3	7	14
Relay (Part 25) Terminal (7) (Purple Wire)	4	9	9
Power Supply 24V Neg Out (Part 27) (Brown Wire)	6	12	11
Power Supply (Part 27) 115 VAC Terminal (2) (Black Wire)	1	13	13
Power Supply NEUT (White or Yellow Wire)	2	15	15
Jumper Terminals (Black Wire)	8 to 12	3 to 6	3 to 7
Jumper Terminals (Purple Wire)	3 to 5	7 to 10	14 to 16
Jumper Terminals (Red Wire)	NC	NC	1 to 2
Jumper Terminals (White Wire)	NC	NC	NC

- B. Installation of Safety Barrier Switch with Mounting Bracket
 - 1. At the balloon inflation building, locate the main power breaker and turn off the AC power to the inflation building.
 - 2. Open the lid of the hydrogen safety switch by loosening the two (2) plastic fasteners (figure 1).
 - 3. With a VOM, verify no AC power exists at TB1 terminals 1 and 2 inside the hydrogen safety switch.
 - 4. Loosen the clamps on rail mount and remove old safety barrier switch by sliding off the right end of the rail mount (figure 2).
 - 5. Remove leads from terminals of old safety barrier switch (figure 2).
 - 6. Remove terminal lugs if necessary and strip insulation to expose approximately ¼ inch of wire.
 - 7. Place leads onto terminals of the SB9102 mounting bracket as shown in table 2 and in wiring diagram (J407-SCHEMATIC).
 - 8. Insert the safety barrier switch P/N SB0728 into the mounting bracket.

Table 2

Control Box Part	Terminal	Wire Color	Safety Barrier Switch Position
TB2	4	Orange	21
TB2	5	Blue	11
Relay (Part 25)	6	Purple or Red	23
Power Supply	24 V Neg out	Brown	13

This completes the installation of the amplifier switch or safety barrier switch.

REPORTING MODIFICATION

Report the completed modification on a WS Form A-26, according to instructions provided in Engineering Handbook No. 4 (EHB-4), Engineering Management Reporting System (EMRS), Part 2, and appendix J. A sample WS Form A-26 is attached. As an additional guide, refer to the following table:

Block #	Block Type	Information		
5	Description	Installed the amplifier switch or barrier safety switch		
7	Equipment Code	ART1 or ART-2 (as appropriate)		
8	Serial Number	Use appropriate serial number		
17a	Modification number	28		

Mark Paese (Acting)
Chief, Maintenance, Logistics, and Acquisition Division

Attachment A - WS Form A-26 Sample
Attachment B - Hydrogen Safety Switch Schematics
File j407SCH
File j407SCH1
File j407SCH2

ENGINEERING HANDBOOK 9 SECTION 2.3

Attachment A

WS FORM A26 (4/94)	WS FORM A -26 (4/94) NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL MEATHER SERVICE ENGINEERING MANAGEMENT REPORTING SYSTEM MAINTENANCE RECORD					G	Document Number G 49978			
aciici ai					e Date / 29 / 02	Time 1100				
5. Description Installation of Amplifier Switch and Safety Barrier Switch, I.A.W. Automatic Radiotheodolite Modification Note 26										
Lyuipinent	FFC 7. E	Equipment Code ART2	8. Seria	nl Number 012		9. TM M		10. AT		ow Mal.)99
1 2. EQUIPMENT OPERATIONAL STATUS TIMES a. Fully Operational b. Logistics Delay Partly Operational C. All Other d. Logistics Delay Not Operational 2:00										
13. Parts Failure Information						14. Work Load Information				
Block # ASN		h.	NSN		TM	AT How Mal	Otsz	g. Maint. Hrs.	Туре	Staff Hrs.
1									a. Routine	
3							-		b. Non- routine	
4									d. Misc.	2:00
5									e. Overtime	
Miscellaneous Installed Amplifier Switch and Safety Barrier switch I.A.W.							16. Initials			
17. SPECIAL PURPOSE REPORTING	a. Mod. No. b. Mod./Act./Deact.Date 1/29/02		c.	d.		e.	e.			
18. CONFIGURATION MGMT. REPORTING (use as directed)	CONFIGURATION MGMT.			Serial Number (Old Part) Serial Number (New Part)				w Part)		

EHB-9 Issuance 02-07 08/27/02

Attachment B

Hydrogen Safety Switch Schematics File j407SCH File j407SCH1 File j407SCH2

